

SNDT Women's University

1, Nathibai Thackersey Road,

Mumbai 400 020

Phone: +91 22 2203 1879

Fax: +91 22 2201 8226



श्रीमती ना. दा. ठाकरसी विद्यापीठ

१, नाथीबाई ठाकरसी मार्ग

मुंबई ४०० ०२०

Telegram: UNIWOMEN

Website: sndt.ac.in

Estate Section/2025-26/226

October 18th, 2025

SUB: Quotation for Site Development work for Students seating near playground area at SNDT Women's University, Pune Campus.

Madam/Sir,

Sealed quotations are invited for Quotation for "Site Development work for Students seating near playground area at SNDT Women's University, Pune Campus." Interested authorized vendors are supposed to submit their quote along with their detail profile in the format given in "Annexure A" on their company letter head. Quotation should be submitted to the office of "The Registrar" at Churchgate campus on or before **07th November 2025** Contractor should submit their quotes in **two envelopes** enclosed in single envelope along with Technical bid envelope & financial bid envelope. Subject should be mentioned on each envelop.

Envelop may contains following documents in respective envelop:

A) Technical Bid

- i. Profile of the vendor
- ii. Work Experience Certificate from the concerned the organization where work has been executed.
- iii. GST Certificate
- iv. PAN Copy
- v. If GST is not applicable then declaration of the same.
- vi. If GST is applicable, then No Dues Certificate authorized by a Chartered Accountant

B) Financial Bid

- vii. Mentioning including all taxes
- viii. If required work is mentioned component wise then the amount is to be given component wise in the prescribed format.

Quotation should be submitted in closed envelop and on top write the subject. As mentioned in the notification.

The University reserves the right to reject any or all quotations without assigning any reasons thereof.

Regards,


Prof. Vilas D. Nandavadekar
Registrar
SNDT Women's University
Mumbai - 20

(Offer should filled on letter head)
Annexure A

To,

The Registrar,
SNDT Women's University,
Churchgate, Mumbai

Sub: Quotation for Site Development work for Students seating near playground area at SNDT Women's University, Pune Campus.

Respected Madam/Sir,

With reference to subject cited above we would like to furnish our quote with best rate possible as below:

Sr. No.	Description of work	Qty.	Unit	Rate	Amount
1	Excavation for foundation in earth, soil of all types and soft murum including removing the excavated material upto a distance of 50 metres behind the building area and stacking and spreading as directed and necessary back filling ramming including sharing and shrutting etc.complete.	144.00	Cum		
2	Providing dry/trap,granite/gneiss rubble stone soling 15 cm to 20 cm thick including hand packing and compacting etc.complete	62.00	Cum		
3	Filling in plinth and floors with contractors material/brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc	19.00	Cum		
4	Providing and laying cast in situ/Ready Mix cement concrete in M20 of trap/granite/quartzite/gnnnnneiss metal for foundation and bedding/steps including steel centering, formwork,laying/pumping.compacting roughening them if special finish is to be provided, finishing uneven and honeycombed surface and curing etc. Complete The cement Mortar 1:3 plaster is considered for rendering uneven and honeycombed surface,only Newly laid cdoncrete shall be covered by gunny bag,plastic tarpaulin etc. (Wooden centering Will not be allowed.), with fully automatic micro processor based OPLC with SCADA enabled reversible Drum Type mixer/concrete Batch mix plant (Pan mixer)etc.complete With fine aggregate (Crushed sand VSI Grade)	31.00	Cum		
5	Providing rough cast cement plaster externally in two coats to concrete, bricks or stone machinery	240.00	Sqm		

	surface in all positions with base coats of 12 to 15 mm thick in com 1:4 and rough cast treatment 12 mm thick in propotion 1.1,1/2:3 including scaffolding and curry				
6	Providing uncoursed rubble masonry of trap/quartzite/gneiss in cement mortar 1:6 in foundation and plinth of inner walls/in plinth of external wall including bailing out water manually striking joints on un exposed faces and watering etc.complete.	58.00	Cum		
7	Providing trac pointing with cement mortar 1:3 for tsone /brick machinery including scapffolding and quarry etc.complete	96.00	Sqm		
	Total				
	Taxes will be paid at actual at the prevailing time.				
	Net Total				